# Nexora Build – Construction Estimate

| | |
|---|---|
| **Project** | 30x40 Residential House (PRJ-0002) |
| **Location** | Thanjavur, Thanjavur, Tamil Nadu |
| **Estimate** | Initial estimate – version 1 |
| **Rates** | Tamil Nadu · Standard specification |
| **Structure** | RCC framed · masonry: brick |
| **Built-up area** | 2,000 sq ft (185.8 m²) |
| **Total cost** | Rs. 39,59,379 |
| **Cost per sq ft** | Rs. 1,980 |
| **Duration** | 7 months (approx.) |
| **Generated** | 18 Oct 2026 06:28 |

| Cost head | Amount (Rs.) |
|---|---|
| Materials | 27,24,470 |
| Labour | 9,58,535 |
| Equipment | 85,563 |
| Material transport & loading (2% of materials) | 54,489 |
| Temporary water + EB (7 months) | 21,000 |
| Contingency (3%) | 1,15,322 |
| Contractor margin (0%) | 0 |
| GST (0%) | 0 |
| Plan approval & fees (as entered) | 0 |
| **GRAND TOTAL** | **39,59,379** |

| Key quantity | Qty |
|---|---|
| Cement | 870 bags |
| Steel | 8,432 kg |
| Bricks | 35,842 nos |
| M-Sand | 63.0 m³ |
| P-Sand | 16.8 m³ |
| Aggregate | 73.3 m³ |
| Labour | 1,141 man-days |

| Floor / Part | Total (Rs.) |
|---|---|
| Foundation | 4,41,237 |
| Plinth | 1,32,223 |
| Ground Floor | 14,07,595 |
| First Floor | 12,04,413 |
| Terrace | 60,296 |
| External | 3,74,404 |
| Site | 1,48,400 |

## Assumptions

- Building footprint taken with the plot's proportion (0.75).
- Floor height 10 ft; plinth 1.5 ft above ground; foundation depth 1.5 m.
- Internal walls ≈ 0.28 m per m² of floor; toilet partitions 115 mm; external walls 230 mm.
- Door / window sizes: main 1.0×2.1 m, room 0.9×2.1 m, toilet 0.75×2.1 m; bedroom window 1.5×1.2 m.

- Concrete M20 (1:1.5:3) for all RCC; PCC 1:4:8 under foundations; brickwork CM 1:6, 460 bricks per $m^3$.
- Wastage included: cement 2%, steel 3%, sand 5%, bricks 5%, tiles 8%.
- RCC frame: 20 columns (4×5 grid, ≈3.6 m spacing), column 230×380 mm, footing 1.5×1.5×0.4 m – preliminary sizes, final sizes from structural design.
- Compound wall length = plot perimeter minus 3.6 m gate = 39.1 m, 1.5 m high.
- Plan approval / permit fees not included (enter them if known).
- No contractor margin (owner-managed construction). Set a % if a contractor builds it.
- Preliminary estimate from a standard layout model. Quantities will be recalculated from the actual drawing in Design Studio. Structural sizes must be confirmed by a qualified engineer.

# Bill of Quantities (BOQ)

| Sl | Floor | Description | Qty | Unit | Rate | Material | Labour | Equip. | Amount |
|---|---|---|---|---|---|---|---|---|---|
| 1 | Foundation | Excavation for footings & plinth beam (JCB + manual dressing) | 147.03 | m³ | 128 | 0 | 11,763 | 7,058 | 18,820 |
| 2 | Foundation | Anti-termite treatment | 92.9 | m² | 35 | 3,252 | 0 | 0 | 3,252 |
| 3 | Foundation | PCC 1:4:8 – under footings | 5.78 | m³ | 4,961 | 20,293 | 7,687 | 694 | 28,674 |
| 4 | Foundation | RCC M20 – Footings | 18.0 | m³ | 7,441 | 98,796 | 31,320 | 3,825 | 1,33,941 |
| 5 | Foundation | Reinforcement (TMT) – Footings | 1,440.0 | kg | 80 | 99,043 | 15,552 | 0 | 1,14,595 |
| 6 | Foundation | Centring & shuttering – Footings | 48.0 | m² | 466 | 12,000 | 10,368 | 0 | 22,368 |
| 7 | Foundation | RCC M20 – Columns up to plinth | 2.71 | m³ | 7,441 | 14,871 | 4,714 | 576 | 20,161 |
| 8 | Foundation | Reinforcement (TMT) – Columns up to plinth | 487.69 | kg | 80 | 33,543 | 5,267 | 0 | 38,811 |
| 9 | Foundation | Centring & shuttering – Columns up to plinth | 37.82 | m² | 466 | 9,455 | 8,169 | 0 | 17,624 |
| 10 | Plinth | RCC M20 – Plinth beam 230×300 | 3.76 | m³ | 7,441 | 20,663 | 6,551 | 800 | 28,014 |
| 11 | Plinth | Reinforcement (TMT) – Plinth beam 230×300 | 489.42 | kg | 80 | 33,662 | 5,286 | 0 | 38,948 |
| 12 | Plinth | Centring & shuttering – Plinth beam 230×300 | 32.74 | m² | 466 | 8,184 | 7,071 | 0 | 15,255 |
| 13 | Foundation | Backfilling with excavated earth, compacted | 102.46 | m³ | 200 | 0 | 20,492 | 0 | 20,492 |
| 14 | Plinth | Plinth filling (earth/gravel) 300 mm, compacted | 27.87 | m³ | 740 | 13,935 | 6,689 | 0 | 20,624 |
| 15 | Plinth | PCC 1:4:8 – flooring bed 75 mm at ground level | 5.92 | m³ | 4,961 | 20,793 | 7,877 | 711 | 29,381 |
| 16 | Foundation | Disposal of surplus earth | 44.57 | m³ | 505 | 0 | 0 | 22,500 | 22,500 |
| 17 | Ground Floor | RCC M20 – Columns | 5.33 | m³ | 7,441 | 29,243 | 9,271 | 1,132 | 39,646 |
| 18 | Ground Floor | Reinforcement (TMT) – Columns | 959.02 | kg | 80 | 65,962 | 10,357 | 0 | 76,319 |
| 19 | Ground Floor | Centring & shuttering – Columns | 74.37 | m² | 466 | 18,593 | 16,064 | 0 | 34,657 |
| 20 | Ground Floor | RCC M20 – Beams 230×450 | 4.08 | m³ | 7,441 | 22,385 | 7,097 | 867 | 30,349 |
| 21 | Ground Floor | Reinforcement (TMT) – Beams 230×450 | 611.77 | kg | 80 | 42,078 | 6,607 | 0 | 48,685 |
| 22 | Ground Floor | Centring & shuttering – Beams 230×450 | 48.01 | m² | 466 | 12,004 | 10,371 | 0 | 22,375 |
| 23 | Ground Floor | RCC M20 – Roof slab 125 mm (incl. sunshade/projection 5%) | 12.19 | m³ | 7,441 | 66,926 | 21,217 | 2,591 | 90,734 |
| 24 | Ground Floor | Reinforcement (TMT) – Roof slab 125 mm (incl. sunshade/projection 5%) | 1,097.42 | kg | 80 | 75,480 | 11,852 | 0 | 87,332 |
| 25 | Ground Floor | Centring & shuttering – Roof slab 125 mm (incl. sunshade/projection 5%) | 97.55 | m² | 466 | 24,387 | 21,070 | 0 | 45,457 |
| 26 | Ground Floor | RCC M20 – Lintels 230×150 | 0.59 | m³ | 7,441 | 3,257 | 1,033 | 126 | 4,416 |

| Sl | Floor | Description | Qty | Unit | Rate | Material | Labour | Equip. | Amount |
|---|---|---|---|---|---|---|---|---|---|
| 27 | Ground Floor | Reinforcement (TMT) – Lintels 230×150 | 41.54 | kg | 80 | 2,857 | 449 | 0 | 3,306 |
| 28 | Ground Floor | Centring & shuttering – Lintels 230×150 | 9.12 | m² | 466 | 2,279 | 1,969 | 0 | 4,248 |
| 29 | Ground Floor | RCC M20 – Sunshades 600 mm | 0.5 | m³ | 7,441 | 2,766 | 877 | 107 | 3,750 |
| 30 | Ground Floor | Reinforcement (TMT) – Sunshades 600 mm | 35.28 | kg | 80 | 2,427 | 381 | 0 | 2,808 |
| 31 | Ground Floor | Centring & shuttering – Sunshades 600 mm | 7.39 | m² | 466 | 1,848 | 1,597 | 0 | 3,445 |
| 32 | Ground Floor | RCC M20 – Staircase | 2.0 | m³ | 7,441 | 10,977 | 3,480 | 425 | 14,882 |
| 33 | Ground Floor | Reinforcement (TMT) – Staircase | 200.0 | kg | 80 | 13,756 | 2,160 | 0 | 15,916 |
| 34 | Ground Floor | Centring & shuttering – Staircase | 8 | m² | 466 | 2,000 | 1,728 | 0 | 3,728 |
| 35 | Ground Floor | Brick masonry 230 mm in CM 1:6 – walls | 32.68 | m³ | 7,517 | 1,94,186 | 51,473 | 0 | 2,45,659 |
| 36 | Ground Floor | Brick partition 115 mm in CM 1:4 – walls | 9.32 | m² | 901 | 6,590 | 1,808 | 0 | 8,398 |
| 37 | Ground Floor | Internal plaster 12 mm CM 1:6 – walls | 209.97 | m² | 195 | 14,531 | 26,456 | 0 | 40,987 |
| 38 | Ground Floor | External plaster 20 mm CM 1:4 (2 coats) – outer walls | 127.92 | m² | 313 | 16,970 | 23,026 | 0 | 39,996 |
| 39 | Ground Floor | Ceiling plaster 6 mm CM 1:3 – ceiling | 85.47 | m² | 206 | 3,790 | 13,846 | 0 | 17,636 |
| 40 | Ground Floor | Vitrified floor tiles on CM 1:4 bed (incl. skirting) | 78.97 | m² | 1,162 | 76,002 | 15,794 | 0 | 91,796 |
| 41 | Ground Floor | Wall tiles – toilets (2.1 m) & kitchen dado | 32.8 | m² | 998 | 24,994 | 7,741 | 0 | 32,734 |
| 42 | Ground Floor | Granite – kitchen counter & staircase treads/risers | 7.8 | m² | 2,445 | 16,731 | 2,340 | 0 | 19,071 |
| 43 | Ground Floor | Waterproofing – toilets | 9.6 | m² | 154 | 960 | 518 | 0 | 1,478 |
| 44 | Ground Floor | Interior painting – putty, primer, 2 coats emulsion (walls + ceiling) | 295.44 | m² | 150 | 27,919 | 16,397 | 0 | 44,315 |
| 45 | Ground Floor | Exterior painting – primer + 2 coats | 127.92 | m² | 200 | 16,118 | 9,466 | 0 | 25,584 |
| 46 | Ground Floor | Main door with frame & hardware | 1 | nos | 32,525 | 31,500 | 1,025 | 0 | 32,525 |
| 47 | Ground Floor | Room doors (flush) with frame & hardware | 2 | nos | 14,525 | 27,000 | 2,050 | 0 | 29,050 |
| 48 | Ground Floor | Toilet doors (PVC/FRP) with frame | 2 | nos | 8,525 | 15,000 | 2,050 | 0 | 17,050 |
| 49 | Ground Floor | Windows & ventilators with glass | 8.34 | m² | 6,450 | 50,040 | 3,753 | 0 | 53,793 |
| 50 | Ground Floor | MS grills for windows | 125.1 | kg | 106 | 11,884 | 1,401 | 0 | 13,286 |
| 51 | Ground Floor | Enamel paint – doors & grills | 21.28 | m² | 155 | 2,021 | 1,277 | 0 | 3,298 |
| 52 | Ground Floor | Toilet – sanitary fittings set | 2 | nos | 25,000 | 50,000 | 0 | 0 | 50,000 |
| 53 | Ground Floor | Toilet – water supply & drainage piping | 2 | nos | 16,900 | 24,000 | 9,800 | 0 | 33,800 |

| Sl | Floor | Description | Qty | Unit | Rate | Material | Labour | Equip. | Amount |
|---|---|---|---|---|---|---|---|---|---|
| 54 | Ground Floor | Kitchen sink, tap & piping | 1 | nos | 11,450 | 9,000 | 2,450 | 0 | 11,450 |
| 55 | Ground Floor | Electrical points (conduit, wiring, switches) | 44 | point | 1,194 | 39,600 | 12,936 | 0 | 52,536 |
| 56 | Ground Floor | Distribution board with MCBs | 1 | nos | 11,100 | 10,000 | 1,100 | 0 | 11,100 |
| 57 | First Floor | RCC M20 – Columns | 5.33 | m³ | 7,441 | 29,243 | 9,271 | 1,132 | 39,646 |
| 58 | First Floor | Reinforcement (TMT) – Columns | 959.02 | kg | 80 | 65,962 | 10,357 | 0 | 76,319 |
| 59 | First Floor | Centring & shuttering – Columns | 74.37 | m² | 466 | 18,593 | 16,064 | 0 | 34,657 |
| 60 | First Floor | RCC M20 – Beams 230×450 | 4.08 | m³ | 7,441 | 22,385 | 7,097 | 867 | 30,349 |
| 61 | First Floor | Reinforcement (TMT) – Beams 230×450 | 611.77 | kg | 80 | 42,078 | 6,607 | 0 | 48,685 |
| 62 | First Floor | Centring & shuttering – Beams 230×450 | 48.01 | m² | 466 | 12,004 | 10,371 | 0 | 22,375 |
| 63 | First Floor | RCC M20 – Roof slab 125 mm (incl. sunshade/projection 5%) | 12.19 | m³ | 7,441 | 66,926 | 21,217 | 2,591 | 90,734 |
| 64 | First Floor | Reinforcement (TMT) – Roof slab 125 mm (incl. sunshade/projection 5%) | 1,097.42 | kg | 80 | 75,480 | 11,852 | 0 | 87,332 |
| 65 | First Floor | Centring & shuttering – Roof slab 125 mm (incl. sunshade/projection 5%) | 97.55 | m² | 466 | 24,387 | 21,070 | 0 | 45,457 |
| 66 | First Floor | RCC M20 – Lintels 230×150 | 0.29 | m³ | 7,441 | 1,591 | 504 | 62 | 2,156 |
| 67 | First Floor | Reinforcement (TMT) – Lintels 230×150 | 20.29 | kg | 80 | 1,395 | 219 | 0 | 1,614 |
| 68 | First Floor | Centring & shuttering – Lintels 230×150 | 4.45 | m² | 466 | 1,113 | 962 | 0 | 2,075 |
| 69 | First Floor | RCC M20 – Sunshades 600 mm | 0.22 | m³ | 7,441 | 1,186 | 376 | 46 | 1,607 |
| 70 | First Floor | Reinforcement (TMT) – Sunshades 600 mm | 15.12 | kg | 80 | 1,040 | 163 | 0 | 1,203 |
| 71 | First Floor | Centring & shuttering – Sunshades 600 mm | 3.17 | m² | 466 | 792 | 684 | 0 | 1,476 |
| 72 | First Floor | RCC M20 – Staircase to terrace + headroom | 1.2 | m³ | 7,441 | 6,586 | 2,088 | 255 | 8,929 |
| 73 | First Floor | Reinforcement (TMT) – Staircase to terrace + headroom | 120.0 | kg | 80 | 8,254 | 1,296 | 0 | 9,550 |
| 74 | First Floor | Centring & shuttering – Staircase to terrace + headroom | 6 | m² | 466 | 1,500 | 1,296 | 0 | 2,796 |
| 75 | First Floor | Brick masonry 230 mm in CM 1:6 – walls | 35.88 | m³ | 7,517 | 2,13,161 | 56,503 | 0 | 2,69,664 |
| 76 | First Floor | Brick partition 115 mm in CM 1:4 – walls | 4.66 | m² | 901 | 3,295 | 904 | 0 | 4,199 |
| 77 | First Floor | Internal plaster 12 mm CM 1:6 – walls | 222.87 | m² | 195 | 15,424 | 28,081 | 0 | 43,505 |
| 78 | First Floor | External plaster 20 mm CM 1:4 (2 coats) – outer walls | 115.94 | m² | 313 | 15,381 | 20,870 | 0 | 36,251 |
| 79 | First Floor | Ceiling plaster 6 mm CM 1:3 – ceiling | 85.47 | m² | 206 | 3,790 | 13,846 | 0 | 17,636 |
| 80 | First Floor | Vitrified floor tiles on CM 1:4 bed (incl. skirting) | 78.97 | m² | 1,162 | 76,002 | 15,794 | 0 | 91,796 |

| Sl | Floor | Description | Qty | Unit | Rate | Material | Labour | Equip. | Amount |
|---|---|---|---|---|---|---|---|---|---|
| 81 | First Floor | Wall tiles – toilets (2.1 m) & kitchen dado | 15.5 | m² | 998 | 11,811 | 3,658 | 0 | 15,469 |
| 82 | First Floor | Waterproofing – toilets & terrace | 109.39 | m² | 154 | 10,939 | 5,907 | 0 | 16,846 |
| 83 | First Floor | Interior painting – putty, primer, 2 coats emulsion (walls + ceiling) | 308.34 | m² | 150 | 29,138 | 17,113 | 0 | 46,250 |
| 84 | First Floor | Exterior painting – primer + 2 coats | 115.94 | m² | 200 | 14,609 | 8,580 | 0 | 23,188 |
| 85 | First Floor | Room doors (flush) with frame & hardware | 2 | nos | 14,525 | 27,000 | 2,050 | 0 | 29,050 |
| 86 | First Floor | Toilet doors (PVC/FRP) with frame | 1 | nos | 8,525 | 7,500 | 1,025 | 0 | 8,525 |
| 87 | First Floor | Windows & ventilators with glass | 2.79 | m² | 6,450 | 16,740 | 1,256 | 0 | 17,996 |
| 88 | First Floor | MS grills for windows | 41.85 | kg | 106 | 3,976 | 469 | 0 | 4,444 |
| 89 | First Floor | Enamel paint – doors & grills | 11.11 | m² | 155 | 1,055 | 666 | 0 | 1,721 |
| 90 | First Floor | Toilet – sanitary fittings set | 1 | nos | 25,000 | 25,000 | 0 | 0 | 25,000 |
| 91 | First Floor | Toilet – water supply & drainage piping | 1 | nos | 16,900 | 12,000 | 4,900 | 0 | 16,900 |
| 92 | First Floor | Electrical points (conduit, wiring, switches) | 15 | point | 1,194 | 13,500 | 4,410 | 0 | 17,910 |
| 93 | First Floor | Distribution board with MCBs | 1 | nos | 11,100 | 10,000 | 1,100 | 0 | 11,100 |
| 94 | Terrace | Brick partition 115 mm in CM 1:4 – terrace parapet 0.9 m | 35.06 | m² | 901 | 24,789 | 6,801 | 0 | 31,591 |
| 95 | Terrace | Internal plaster 12 mm CM 1:6 – parapet inner face | 35.06 | m² | 195 | 2,426 | 4,417 | 0 | 6,844 |
| 96 | Terrace | External plaster 20 mm CM 1:4 (2 coats) – parapet outer face | 35.06 | m² | 313 | 4,651 | 6,311 | 0 | 10,962 |
| 97 | Terrace | Overhead tank 1000 L with fittings | 1,000 | litre | 11 | 9,000 | 1,900 | 0 | 10,900 |
| 98 | External | Underground sump 6000 L (complete) + pump | 6,000 | litre | 12 | 72,000 | 1,100 | 0 | 73,100 |
| 99 | External | Septic tank + soak pit (complete) | 1 | nos | 60,000 | 60,000 | 0 | 0 | 60,000 |
| 100 | External | Earthing pits | 2 | nos | 6,550 | 12,000 | 1,100 | 0 | 13,100 |
| 101 | External | EB service connection & meter board | 1 | nos | 15,000 | 15,000 | 0 | 0 | 15,000 |
| 102 | External | Rain water harvesting pit (TN mandatory) | 1 | nos | 20,000 | 20,000 | 0 | 0 | 20,000 |
| 103 | External | Compound wall 1.5 m high (complete) | 39.07 | rmt | 3,875 | 1,17,216 | 34,188 | 0 | 1,51,404 |
| 104 | External | MS gate (fabricated & painted) | 1 | nos | 41,800 | 40,000 | 1,800 | 0 | 41,800 |
| 105 | Site | Construction water (tanker loads) | 56 | load | 700 | 0 | 0 | 39,200 | 39,200 |
| 106 | Site | Watchman & curing during construction | 182 | day | 600 | 0 | 1,09,200 | 0 | 1,09,200 |
| | | **TOTAL (before extras)** | | | | **27,24,470** | **9,58,535** | **85,563** | **37,68,568** |

## Materials (incl. wastage)

| Material | Qty | Unit | Rate | Amount |
|---|---|---|---|---|
| TMT steel bars | 8,431.34 | kg | 66 | 5,56,468 |
| Bricks (chamber / wire-cut) | 35,841.89 | nos | 10 | 3,58,419 |
| Cement (PPC / OPC 53) | 869.82 | bag | 400 | 3,47,930 |
| Centring sheets / props / plywood (hire + consumables) | 596.55 | m2 | 250 | 1,49,138 |
| Floor tiles (vitrified) | 180.8 | m2 | 750 | 1,35,603 |
| Compound wall materials (1.5 m high, per running metre) | 39.07 | rmt | 3,000 | 1,17,216 |
| M-Sand (concrete / masonry) | 63.0 | m3 | 1,850 | 1,16,554 |
| Blue metal / jelly 20 mm | 62.71 | m3 | 1,600 | 1,00,332 |
| Sanitary set per toilet (EWC, basin, taps, shower) | 3.0 | nos | 25,000 | 75,000 |
| Windows (aluminium / UPVC with glass) | 11.13 | m2 | 6,000 | 66,780 |
| Underground sump (complete, per litre) | 6,000.0 | litre | 10 | 60,000 |
| Septic tank + soak pit (complete) | 1.0 | nos | 60,000 | 60,000 |
| Interior paint system (putty + primer + 2 coats emulsion) | 633.96 | m2 | 90 | 57,056 |
| Electrical point (conduit, wire, switch, box) | 59.0 | point | 900 | 53,100 |
| Internal flush door with frame | 4.0 | nos | 12,000 | 48,000 |
| MS gate (fabricated, painted) | 1.0 | nos | 40,000 | 40,000 |
| P-Sand (plastering) | 16.83 | m3 | 2,150 | 36,190 |
| Plumbing pipes & fittings per toilet | 3.0 | nos | 12,000 | 36,000 |
| Wall tiles (toilet / kitchen dado) | 52.16 | m2 | 650 | 33,907 |
| Exterior paint system (primer + 2 coats) | 256.06 | m2 | 120 | 30,727 |
| Main door with frame (complete) | 1.0 | nos | 30,000 | 30,000 |
| Distribution board + MCBs (per floor) | 2.0 | nos | 10,000 | 20,000 |
| Rain water harvesting pit (complete) | 1.0 | nos | 20,000 | 20,000 |
| Toilet door (PVC / FRP) with frame | 3.0 | nos | 6,000 | 18,000 |
| Granite (kitchen top, steps) | 8.58 | m2 | 1,950 | 16,731 |
| MS window grills | 166.95 | kg | 95 | 15,860 |

| Material | Qty | Unit | Rate | Amount |
|---|---|---|---|---|
| EB service connection & meter board | 1.0 | nos | 15,000 | 15,000 |
| Jelly 40 mm (PCC) | 10.61 | m3 | 1,400 | 14,850 |
| Filling earth / gravel | 27.87 | m3 | 500 | 13,935 |
| Door hardware set (hinges, locks, handles) | 8.0 | nos | 1,500 | 12,000 |
| Water pump motor 1 HP + fittings | 1.0 | nos | 12,000 | 12,000 |
| Earthing pit | 2.0 | nos | 6,000 | 12,000 |
| Waterproofing (toilets, terrace) | 118.99 | m2 | 100 | 11,899 |
| Kitchen sink + tap + piping | 1.0 | nos | 9,000 | 9,000 |
| Overhead water tank | 1,000.0 | litre | 9 | 9,000 |
| Binding wire | 81.86 | kg | 80 | 6,549 |
| Anti-termite chemical treatment | 92.9 | m2 | 35 | 3,252 |
| Enamel paint (doors, grills) | 32.38 | m2 | 95 | 3,076 |
| Tile adhesive / grout | 48.3 | m2 | 60 | 2,898 |

## Labour (man-days × TN day wage)

| Labour trade | Man-days | Wage | Amount |
|---|---|---|---|
| Helper – male (Chithal) | 362.95 | 800 | 2,90,384 |
| Mason (Kothanaar) | 164.09 | 1,100 | 1,80,478 |
| Helper – female (Chithal) | 206.82 | 700 | 1,44,796 |
| Watchman / curing | 182.0 | 600 | 1,09,200 |
| Centring carpenter | 71.58 | 1,000 | 71,586 |
| Bar bender | 49.1 | 1,000 | 49,115 |
| Painter | 43.76 | 1,000 | 43,744 |
| Tile layer | 23.25 | 1,200 | 27,891 |
| Electrician | 13.62 | 1,100 | 14,982 |
| Plumber | 12.5 | 1,100 | 13,750 |
| Carpenter (doors / windows) | 9.34 | 1,100 | 10,273 |

| Labour trade | Man-days | Wage | Amount |
|---|---|---|---|
| Welder / fabricator | 2.33 | 1,000 | 2,336 |