Praganya Construction

Proprietor: Nishanth S · 98xxxxxx

Thanjavur

CONSTRUCTION COST ESTIMATE

Particulars	Details
Name of owner / client	Mr. Kumar
Project	G+3 Residential Apartments (PRJ-0027)
Site location	Thiruvarur, Thiruvarur, Tamil Nadu
Plot size	40 x 60 ft
Floors	G+3
Structure	RCC framed
Specification	Standard
Total built-up area	5,800 sq ft (538.8 m2)
Rates	Tamil Nadu market rates
Date	03-11-2026

Area statement

Floor	Built-up (sq ft)	Carpet (approx.)	Remarks
Ground Floor	1,450	1,132	2 bed, 2 toilet, kitchen, hall
First Floor	1,450	1,132	2 bed, 2 toilet, kitchen, hall
Second Floor	1,450	1,132	2 bed, 2 toilet, kitchen, hall
Third Floor	1,450	1,132	2 bed, 2 toilet, kitchen, hall
Total	**5,800**	**4,528**	

Abstract of cost

S.No	Description of work	Amount (Rs.)	%
1	Civil Works	80,67,009	72.4%
2	Finishes	14,57,782	13.1%
3	Doors & Windows	6,82,159	6.1%
4	Plumbing	5,40,371	4.9%
5	Electrical	3,64,604	3.3%
6	External Works	25,800	0.2%
	TOTAL ESTIMATED COST	**1,11,37,724**	**100%**

Cost per sq ft (built-up): **Rs. 1,920** · Approx. duration: 14 months

Main materials (approx.)

Material	Quantity
Cement	2,207 bags
Steel	21,959 kg
M-Sand	158.6 m3
P-Sand	41.0 m3
Aggregate	180.9 m3

Material	Quantity
Bricks	90,904 nos

Stage-wise payment schedule

Stage	Description	%	Amount (Rs.)
1	Advance / Mobilization	10%	11,13,772
2	Foundation up to Plinth	15%	16,70,659
3	Ground Floor Roof Slab	14%	15,59,281
4	First Floor Roof Slab	14%	15,59,281
5	Second Floor Roof Slab	14%	15,59,281
6	Third Floor Roof Slab	13%	14,47,904
7	Finishing Works (plaster, flooring, painting)	15%	16,70,659
8	External Works & Handover	5%	5,56,886
	Total	**100%**	**1,11,37,723**

Notes: This estimate is prepared from the proposed plan at current market rates and is indicative. Actual cost can vary with design changes, site conditions, material prices and specifications. Structural sizes are to be confirmed by the structural design.

For Praganya Construction

Nishanth S (Proprietor)