Praganya Construction – Construction Estimate

Proprietor: Nishanth S · 98xxxxxx · Thanjavur

Project	G+3 Residential Apartments (PRJ-0027)
Location	Thiruvarur, Thiruvarur, Tamil Nadu
Estimate	Standard estimate – version 1
Rates	Tamil Nadu · Standard specification
Structure	RCC framed · masonry: brick
Built-up area	5,800 sq ft (538.8 m2)
Total cost	Rs. 1,11,37,724
Cost per sq ft	Rs. 1,920
Duration	14 months (approx.)
Generated	02 Nov 2026 18:41

Cost head	Amount (Rs.)
Materials	62,15,109
Labour	22,43,170
Equipment	1,75,770
Material transport & loading (2% of materials)	1,24,302
Temporary water + EB (14 months)	42,000
Contingency (3%)	2,64,011
Contractor margin (10%)	8,80,035
GST (12%)	11,93,328
Plan approval & fees (as entered)	0
GRAND TOTAL	**1,11,37,724**

Key quantity	Qty
Cement	2,207 bags
Steel	21,959 kg
Bricks	90,904 nos
M-Sand	158.6 m3
P-Sand	41.0 m3
Aggregate	180.9 m3
Labour	2,642 man-days

Floor / Part	Total (Rs.)
Foundation	9,15,086
Plinth	1,78,011
Ground Floor	17,97,135
First Floor	17,68,640
Second Floor	17,68,640
Third Floor	17,63,653
Terrace	97,984
External	48,100
Site	2,96,800

Assumptions

- Building footprint taken with the plot's proportion (0.67).
- Floor height 10 ft; plinth 1.5 ft above ground; foundation depth 1.5 m.
- Internal walls ~ 0.28 m per m2 of floor; toilet partitions 115 mm; external walls 230 mm.
- Door / window sizes: main 1.0×2.1 m, room 0.9×2.1 m, toilet 0.75×2.1 m; bedroom window 1.5×1.2 m.

- Concrete M20 (1:1.5:3) for all RCC; PCC 1:4:8 under foundations; brickwork CM 1:6, 460 bricks per m3.
- Wastage included: cement 2%, steel 3%, sand 5%, bricks 5%, tiles 8%.
- RCC frame: 20 columns (4×5 grid, ~3.6 m spacing), column 300×450 mm, footing 2.1×2.1×0.5 m – preliminary sizes, final sizes from structural design.
- Plan approval / permit fees not included (enter them if known).
- Carpet area = built-up minus wall thickness (230/115 mm walls) minus staircase (10.5 m2 per floor) – approximate; measure from the final drawing.
- Preliminary estimate from a standard layout model. Quantities will be recalculated from the actual drawing in Design Studio. Structural sizes must be confirmed by a qualified engineer.

Bill of Quantities (BOQ)

Sl	Floor	Description	Qty	Unit	Rate	Material	Labour	Equip.	Amount
1	Foundation	Excavation for footings & plinth beam (JCB + manual dressing)	237.6	m3	128	0	19,008	11,405	30,413
2	Foundation	Anti-termite treatment	134.71	m2	35	4,715	0	0	4,715
3	Foundation	PCC 1:4:8 – under footings	10.58	m3	4,961	37,145	14,071	1,270	52,486
4	Foundation	RCC M20 – Footings	44.1	m3	7,441	2,42,049	76,734	9,371	3,28,155
5	Foundation	Reinforcement (TMT) – Footings	3,528.0	kg	80	2,42,656	38,102	0	2,80,758
6	Foundation	Centring & shuttering – Footings	84.0	m2	466	21,000	18,144	0	39,144
7	Foundation	RCC M20 – Columns up to plinth	3.92	m3	7,441	21,488	6,812	832	29,132
8	Foundation	Reinforcement (TMT) – Columns up to plinth	704.7	kg	80	48,469	7,611	0	56,080
9	Foundation	Centring & shuttering – Columns up to plinth	43.5	m2	466	10,875	9,396	0	20,271
10	Plinth	RCC M20 – Plinth beam 230×300	4.83	m3	7,441	26,516	8,406	1,027	35,948
11	Plinth	Reinforcement (TMT) – Plinth beam 230×300	628.03	kg	80	43,196	6,783	0	49,978
12	Plinth	Centring & shuttering – Plinth beam 230×300	42.01	m2	466	10,502	9,074	0	19,576
13	Foundation	Backfilling with excavated earth, compacted	152.16	m3	200	0	30,432	0	30,432
14	Plinth	Plinth filling (earth/gravel) 300 mm, compacted	40.41	m3	740	20,206	9,699	0	29,905
15	Plinth	PCC 1:4:8 – flooring bed 75 mm at ground level	8.59	m3	4,961	30,150	11,422	1,031	42,602
16	Foundation	Disposal of surplus earth	85.45	m3	509	0	0	43,500	43,500
17	Ground Floor	RCC M20 – Columns	8.23	m3	7,441	45,169	14,320	1,749	61,238
18	Ground Floor	Reinforcement (TMT) – Columns	1,481.33	kg	80	1,01,886	15,998	0	1,17,884
19	Ground Floor	Centring & shuttering – Columns	91.44	m2	466	22,860	19,751	0	42,611
20	Ground Floor	RCC M20 – Beams 230×450	5.23	m3	7,441	28,725	9,106	1,112	38,944
21	Ground Floor	Reinforcement (TMT) – Beams 230×450	785.03	kg	80	53,995	8,478	0	62,473
22	Ground Floor	Centring & shuttering – Beams 230×450	61.61	m2	466	15,403	13,308	0	28,711
23	Ground Floor	RCC M20 – Roof slab 125 mm (incl. sunshade/projection 5%)	17.68	m3	7,441	97,043	30,764	3,757	1,31,564
24	Ground Floor	Reinforcement (TMT) – Roof slab 125 mm (incl. sunshade/projection 5%)	1,591.25	kg	80	1,09,447	17,186	0	1,26,632
25	Ground Floor	Centring & shuttering – Roof slab 125 mm (incl. sunshade/projection 5%)	141.44	m2	466	35,361	30,552	0	65,913
26	Ground Floor	RCC M20 – Lintels 230×150	0.59	m3	7,441	3,257	1,033	126	4,416

Sl	Floor	Description	Qty	Unit	Rate	Material	Labour	Equip.	Amount
27	Ground Floor	Reinforcement (TMT) – Lintels 230×150	41.54	kg	80	2,857	449	0	3,306
28	Ground Floor	Centring & shuttering – Lintels 230×150	9.12	m2	466	2,279	1,969	0	4,248
29	Ground Floor	RCC M20 – Sunshades 600 mm	0.5	m3	7,441	2,766	877	107	3,750
30	Ground Floor	Reinforcement (TMT) – Sunshades 600 mm	35.28	kg	80	2,427	381	0	2,808
31	Ground Floor	Centring & shuttering – Sunshades 600 mm	7.39	m2	466	1,848	1,597	0	3,445
32	Ground Floor	RCC M20 – Staircase	2.0	m3	7,441	10,977	3,480	425	14,882
33	Ground Floor	Reinforcement (TMT) – Staircase	200.0	kg	80	13,756	2,160	0	15,916
34	Ground Floor	Centring & shuttering – Staircase	8	m2	466	2,000	1,728	0	3,728
35	Ground Floor	Brick masonry 230 mm in CM 1:6 – walls	44.71	m3	7,517	2,65,673	70,423	0	3,36,096
36	Ground Floor	Brick partition 115 mm in CM 1:4 – walls	9.32	m2	901	6,590	1,808	0	8,398
37	Ground Floor	Internal plaster 12 mm CM 1:6 – walls	292.69	m2	195	20,256	36,879	0	57,135
38	Ground Floor	External plaster 20 mm CM 1:4 (2 coats) – outer walls	157.41	m2	313	20,882	28,333	0	49,215
39	Ground Floor	Ceiling plaster 6 mm CM 1:3 – ceiling	123.93	m2	206	5,496	20,077	0	25,573
40	Ground Floor	Vitrified floor tiles on CM 1:4 bed (incl. skirting)	114.5	m2	1,162	1,10,203	22,901	0	1,33,104
41	Ground Floor	Wall tiles – toilets (2.1 m) & kitchen dado	32.8	m2	998	24,994	7,741	0	32,734
42	Ground Floor	Granite – kitchen counter & staircase treads/risers	7.8	m2	2,445	16,731	2,340	0	19,071
43	Ground Floor	Waterproofing – toilets	9.6	m2	154	960	518	0	1,478
44	Ground Floor	Interior painting – putty, primer, 2 coats emulsion (walls + ceiling)	416.62	m2	150	39,371	23,122	0	62,493
45	Ground Floor	Exterior painting – primer + 2 coats	157.41	m2	200	19,833	11,648	0	31,481
46	Ground Floor	Main door with frame & hardware	1	nos	32,525	31,500	1,025	0	32,525
47	Ground Floor	Room doors (flush) with frame & hardware	2	nos	14,525	27,000	2,050	0	29,050
48	Ground Floor	Toilet doors (PVC/FRP) with frame	2	nos	8,525	15,000	2,050	0	17,050
49	Ground Floor	Windows & ventilators with glass	8.34	m2	6,450	50,040	3,753	0	53,793
50	Ground Floor	MS grills for windows	125.1	kg	106	11,884	1,401	0	13,286
51	Ground Floor	Enamel paint – doors & grills	21.28	m2	155	2,021	1,277	0	3,298
52	Ground Floor	Toilet – sanitary fittings set	2	nos	25,000	50,000	0	0	50,000
53	Ground Floor	Toilet – water supply & drainage piping	2	nos	16,900	24,000	9,800	0	33,800

Sl	Floor	Description	Qty	Unit	Rate	Material	Labour	Equip.	Amount
54	Ground Floor	Kitchen sink, tap & piping	1	nos	11,450	9,000	2,450	0	11,450
55	Ground Floor	Electrical points (conduit, wiring, switches)	44	point	1,194	39,600	12,936	0	52,536
56	Ground Floor	Distribution board with MCBs	1	nos	11,100	10,000	1,100	0	11,100
57	First Floor	RCC M20 – Columns	8.23	m3	7,441	45,169	14,320	1,749	61,238
58	First Floor	Reinforcement (TMT) – Columns	1,481.33	kg	80	1,01,886	15,998	0	1,17,884
59	First Floor	Centring & shuttering – Columns	91.44	m2	466	22,860	19,751	0	42,611
60	First Floor	RCC M20 – Beams 230×450	5.23	m3	7,441	28,725	9,106	1,112	38,944
61	First Floor	Reinforcement (TMT) – Beams 230×450	785.03	kg	80	53,995	8,478	0	62,473
62	First Floor	Centring & shuttering – Beams 230×450	61.61	m2	466	15,403	13,308	0	28,711
63	First Floor	RCC M20 – Roof slab 125 mm (incl. sunshade/projection 5%)	17.68	m3	7,441	97,043	30,764	3,757	1,31,564
64	First Floor	Reinforcement (TMT) – Roof slab 125 mm (incl. sunshade/projection 5%)	1,591.25	kg	80	1,09,447	17,186	0	1,26,632
65	First Floor	Centring & shuttering – Roof slab 125 mm (incl. sunshade/projection 5%)	141.44	m2	466	35,361	30,552	0	65,913
66	First Floor	RCC M20 – Lintels 230×150	0.59	m3	7,441	3,257	1,033	126	4,416
67	First Floor	Reinforcement (TMT) – Lintels 230×150	41.54	kg	80	2,857	449	0	3,306
68	First Floor	Centring & shuttering – Lintels 230×150	9.12	m2	466	2,279	1,969	0	4,248
69	First Floor	RCC M20 – Sunshades 600 mm	0.5	m3	7,441	2,766	877	107	3,750
70	First Floor	Reinforcement (TMT) – Sunshades 600 mm	35.28	kg	80	2,427	381	0	2,808
71	First Floor	Centring & shuttering – Sunshades 600 mm	7.39	m2	466	1,848	1,597	0	3,445
72	First Floor	RCC M20 – Staircase	2.0	m3	7,441	10,977	3,480	425	14,882
73	First Floor	Reinforcement (TMT) – Staircase	200.0	kg	80	13,756	2,160	0	15,916
74	First Floor	Centring & shuttering – Staircase	8	m2	466	2,000	1,728	0	3,728
75	First Floor	Brick masonry 230 mm in CM 1:6 – walls	44.76	m3	7,517	2,65,960	70,499	0	3,36,459
76	First Floor	Brick partition 115 mm in CM 1:4 – walls	9.32	m2	901	6,590	1,808	0	8,398
77	First Floor	Internal plaster 12 mm CM 1:6 – walls	293.11	m2	195	20,285	36,932	0	57,217
78	First Floor	External plaster 20 mm CM 1:4 (2 coats) – outer walls	136.08	m2	313	18,053	24,495	0	42,548
79	First Floor	Ceiling plaster 6 mm CM 1:3 – ceiling	123.93	m2	206	5,496	20,077	0	25,573
80	First Floor	Vitrified floor tiles on CM 1:4 bed (incl. skirting)	114.5	m2	1,162	1,10,203	22,901	0	1,33,104

Sl	Floor	Description	Qty	Unit	Rate	Material	Labour	Equip.	Amount
81	First Floor	Wall tiles – toilets (2.1 m) & kitchen dado	32.8	m2	998	24,994	7,741	0	32,734
82	First Floor	Granite – kitchen counter & staircase treads/risers	7.8	m2	2,445	16,731	2,340	0	19,071
83	First Floor	Waterproofing – toilets	9.6	m2	154	960	518	0	1,478
84	First Floor	Interior painting – putty, primer, 2 coats emulsion (walls + ceiling)	417.04	m2	150	39,410	23,146	0	62,556
85	First Floor	Exterior painting – primer + 2 coats	136.08	m2	200	17,147	10,070	0	27,217
86	First Floor	Room doors (flush) with frame & hardware	3	nos	14,525	40,500	3,075	0	43,575
87	First Floor	Toilet doors (PVC/FRP) with frame	2	nos	8,525	15,000	2,050	0	17,050
88	First Floor	Windows & ventilators with glass	8.34	m2	6,450	50,040	3,753	0	53,793
89	First Floor	MS grills for windows	125.1	kg	106	11,884	1,401	0	13,286
90	First Floor	Enamel paint – doors & grills	20.81	m2	155	1,977	1,249	0	3,226
91	First Floor	Toilet – sanitary fittings set	2	nos	25,000	50,000	0	0	50,000
92	First Floor	Toilet – water supply & drainage piping	2	nos	16,900	24,000	9,800	0	33,800
93	First Floor	Kitchen sink, tap & piping	1	nos	11,450	9,000	2,450	0	11,450
94	First Floor	Electrical points (conduit, wiring, switches)	44	point	1,194	39,600	12,936	0	52,536
95	First Floor	Distribution board with MCBs	1	nos	11,100	10,000	1,100	0	11,100
96	Second Floor	RCC M20 – Columns	8.23	m3	7,441	45,169	14,320	1,749	61,238
97	Second Floor	Reinforcement (TMT) – Columns	1,481.33	kg	80	1,01,886	15,998	0	1,17,884
98	Second Floor	Centring & shuttering – Columns	91.44	m2	466	22,860	19,751	0	42,611
99	Second Floor	RCC M20 – Beams 230×450	5.23	m3	7,441	28,725	9,106	1,112	38,944
100	Second Floor	Reinforcement (TMT) – Beams 230×450	785.03	kg	80	53,995	8,478	0	62,473
101	Second Floor	Centring & shuttering – Beams 230×450	61.61	m2	466	15,403	13,308	0	28,711
102	Second Floor	RCC M20 – Roof slab 125 mm (incl. sunshade/projection 5%)	17.68	m3	7,441	97,043	30,764	3,757	1,31,564
103	Second Floor	Reinforcement (TMT) – Roof slab 125 mm (incl. sunshade/projection 5%)	1,591.25	kg	80	1,09,447	17,186	0	1,26,632
104	Second Floor	Centring & shuttering – Roof slab 125 mm (incl. sunshade/projection 5%)	141.44	m2	466	35,361	30,552	0	65,913
105	Second Floor	RCC M20 – Lintels 230×150	0.59	m3	7,441	3,257	1,033	126	4,416
106	Second Floor	Reinforcement (TMT) – Lintels 230×150	41.54	kg	80	2,857	449	0	3,306
107	Second Floor	Centring & shuttering – Lintels 230×150	9.12	m2	466	2,279	1,969	0	4,248

Sl	Floor	Description	Qty	Unit	Rate	Material	Labour	Equip.	Amount
108	Second Floor	RCC M20 – Sunshades 600 mm	0.5	m3	7,441	2,766	877	107	3,750
109	Second Floor	Reinforcement (TMT) – Sunshades 600 mm	35.28	kg	80	2,427	381	0	2,808
110	Second Floor	Centring & shuttering – Sunshades 600 mm	7.39	m2	466	1,848	1,597	0	3,445
111	Second Floor	RCC M20 – Staircase	2.0	m3	7,441	10,977	3,480	425	14,882
112	Second Floor	Reinforcement (TMT) – Staircase	200.0	kg	80	13,756	2,160	0	15,916
113	Second Floor	Centring & shuttering – Staircase	8	m2	466	2,000	1,728	0	3,728
114	Second Floor	Brick masonry 230 mm in CM 1:6 – walls	44.76	m3	7,517	2,65,960	70,499	0	3,36,459
115	Second Floor	Brick partition 115 mm in CM 1:4 – walls	9.32	m2	901	6,590	1,808	0	8,398
116	Second Floor	Internal plaster 12 mm CM 1:6 – walls	293.11	m2	195	20,285	36,932	0	57,217
117	Second Floor	External plaster 20 mm CM 1:4 (2 coats) – outer walls	136.08	m2	313	18,053	24,495	0	42,548
118	Second Floor	Ceiling plaster 6 mm CM 1:3 – ceiling	123.93	m2	206	5,496	20,077	0	25,573
119	Second Floor	Vitrified floor tiles on CM 1:4 bed (incl. skirting)	114.5	m2	1,162	1,10,203	22,901	0	1,33,104
120	Second Floor	Wall tiles – toilets (2.1 m) & kitchen dado	32.8	m2	998	24,994	7,741	0	32,734
121	Second Floor	Granite – kitchen counter & staircase treads/risers	7.8	m2	2,445	16,731	2,340	0	19,071
122	Second Floor	Waterproofing – toilets	9.6	m2	154	960	518	0	1,478
123	Second Floor	Interior painting – putty, primer, 2 coats emulsion (walls + ceiling)	417.04	m2	150	39,410	23,146	0	62,556
124	Second Floor	Exterior painting – primer + 2 coats	136.08	m2	200	17,147	10,070	0	27,217
125	Second Floor	Room doors (flush) with frame & hardware	3	nos	14,525	40,500	3,075	0	43,575
126	Second Floor	Toilet doors (PVC/FRP) with frame	2	nos	8,525	15,000	2,050	0	17,050
127	Second Floor	Windows & ventilators with glass	8.34	m2	6,450	50,040	3,753	0	53,793
128	Second Floor	MS grills for windows	125.1	kg	106	11,884	1,401	0	13,286
129	Second Floor	Enamel paint – doors & grills	20.81	m2	155	1,977	1,249	0	3,226
130	Second Floor	Toilet – sanitary fittings set	2	nos	25,000	50,000	0	0	50,000
131	Second Floor	Toilet – water supply & drainage piping	2	nos	16,900	24,000	9,800	0	33,800
132	Second Floor	Kitchen sink, tap & piping	1	nos	11,450	9,000	2,450	0	11,450
133	Second Floor	Electrical points (conduit, wiring, switches)	44	point	1,194	39,600	12,936	0	52,536
134	Second Floor	Distribution board with MCBs	1	nos	11,100	10,000	1,100	0	11,100

Sl	Floor	Description	Qty	Unit	Rate	Material	Labour	Equip.	Amount
135	Third Floor	RCC M20 – Columns	8.23	m3	7,441	45,169	14,320	1,749	61,238
136	Third Floor	Reinforcement (TMT) – Columns	1,481.33	kg	80	1,01,886	15,998	0	1,17,884
137	Third Floor	Centring & shuttering – Columns	91.44	m2	466	22,860	19,751	0	42,611
138	Third Floor	RCC M20 – Beams 230×450	5.23	m3	7,441	28,725	9,106	1,112	38,944
139	Third Floor	Reinforcement (TMT) – Beams 230×450	785.03	kg	80	53,995	8,478	0	62,473
140	Third Floor	Centring & shuttering – Beams 230×450	61.61	m2	466	15,403	13,308	0	28,711
141	Third Floor	RCC M20 – Roof slab 125 mm (incl. sunshade/projection 5%)	17.68	m3	7,441	97,043	30,764	3,757	1,31,564
142	Third Floor	Reinforcement (TMT) – Roof slab 125 mm (incl. sunshade/projection 5%)	1,591.25	kg	80	1,09,447	17,186	0	1,26,632
143	Third Floor	Centring & shuttering – Roof slab 125 mm (incl. sunshade/projection 5%)	141.44	m2	466	35,361	30,552	0	65,913
144	Third Floor	RCC M20 – Lintels 230×150	0.59	m3	7,441	3,257	1,033	126	4,416
145	Third Floor	Reinforcement (TMT) – Lintels 230×150	41.54	kg	80	2,857	449	0	3,306
146	Third Floor	Centring & shuttering – Lintels 230×150	9.12	m2	466	2,279	1,969	0	4,248
147	Third Floor	RCC M20 – Sunshades 600 mm	0.5	m3	7,441	2,766	877	107	3,750
148	Third Floor	Reinforcement (TMT) – Sunshades 600 mm	35.28	kg	80	2,427	381	0	2,808
149	Third Floor	Centring & shuttering – Sunshades 600 mm	7.39	m2	466	1,848	1,597	0	3,445
150	Third Floor	RCC M20 – Staircase to terrace + headroom	1.2	m3	7,441	6,586	2,088	255	8,929
151	Third Floor	Reinforcement (TMT) – Staircase to terrace + headroom	120.0	kg	80	8,254	1,296	0	9,550
152	Third Floor	Centring & shuttering – Staircase to terrace + headroom	6	m2	466	1,500	1,296	0	2,796
153	Third Floor	Brick masonry 230 mm in CM 1:6 – walls	44.76	m3	7,517	2,65,960	70,499	0	3,36,459
154	Third Floor	Brick partition 115 mm in CM 1:4 – walls	9.32	m2	901	6,590	1,808	0	8,398
155	Third Floor	Internal plaster 12 mm CM 1:6 – walls	293.11	m2	195	20,285	36,932	0	57,217
156	Third Floor	External plaster 20 mm CM 1:4 (2 coats) – outer walls	136.08	m2	313	18,053	24,495	0	42,548
157	Third Floor	Ceiling plaster 6 mm CM 1:3 – ceiling	123.93	m2	206	5,496	20,077	0	25,573
158	Third Floor	Vitrified floor tiles on CM 1:4 bed (incl. skirting)	114.5	m2	1,162	1,10,203	22,901	0	1,33,104
159	Third Floor	Wall tiles – toilets (2.1 m) & kitchen dado	32.8	m2	998	24,994	7,741	0	32,734
160	Third Floor	Granite – kitchen counter & staircase treads/risers	1.8	m2	2,445	3,861	540	0	4,401
161	Third Floor	Waterproofing – toilets & terrace	158.52	m2	154	15,852	8,560	0	24,413

Sl	Floor	Description	Qty	Unit	Rate	Material	Labour	Equip.	Amount
162	Third Floor	Interior painting – putty, primer, 2 coats emulsion (walls + ceiling)	417.04	m2	150	39,410	23,146	0	62,556
163	Third Floor	Exterior painting – primer + 2 coats	136.08	m2	200	17,147	10,070	0	27,217
164	Third Floor	Room doors (flush) with frame & hardware	3	nos	14,525	40,500	3,075	0	43,575
165	Third Floor	Toilet doors (PVC/FRP) with frame	2	nos	8,525	15,000	2,050	0	17,050
166	Third Floor	Windows & ventilators with glass	8.34	m2	6,450	50,040	3,753	0	53,793
167	Third Floor	MS grills for windows	125.1	kg	106	11,884	1,401	0	13,286
168	Third Floor	Enamel paint – doors & grills	20.81	m2	155	1,977	1,249	0	3,226
169	Third Floor	Toilet – sanitary fittings set	2	nos	25,000	50,000	0	0	50,000
170	Third Floor	Toilet – water supply & drainage piping	2	nos	16,900	24,000	9,800	0	33,800
171	Third Floor	Kitchen sink, tap & piping	1	nos	11,450	9,000	2,450	0	11,450
172	Third Floor	Electrical points (conduit, wiring, switches)	44	point	1,194	39,600	12,936	0	52,536
173	Third Floor	Distribution board with MCBs	1	nos	11,100	10,000	1,100	0	11,100
174	Terrace	Brick partition 115 mm in CM 1:4 – terrace parapet 0.9 m	42.64	m2	901	30,153	8,273	0	38,426
175	Terrace	Internal plaster 12 mm CM 1:6 – parapet inner face	42.64	m2	195	2,951	5,373	0	8,325
176	Terrace	External plaster 20 mm CM 1:4 (2 coats) – parapet outer face	42.64	m2	313	5,657	7,676	0	13,333
177	Terrace	Overhead tank 4000 L with fittings	4,000	litre	9	36,000	1,900	0	37,900
178	External	Earthing pits	2	nos	6,550	12,000	1,100	0	13,100
179	External	EB service connection & meter board	1	nos	15,000	15,000	0	0	15,000
180	External	Rain water harvesting pit (TN mandatory)	1	nos	20,000	20,000	0	0	20,000
181	Site	Construction water (tanker loads)	112	load	700	0	0	78,400	78,400
182	Site	Watchman & curing during construction	364	day	600	0	2,18,400	0	2,18,400
		TOTAL (before extras)				**62,15,109**	**22,43,170**	**1,75,770**	**86,34,049**

Floor-wise BOQ

S.No	Description	Unit	Ground	First	Second	Third	Common	Total	Rate	Amount
1	Excavation for footings & plinth beam (JCB + manual dressing)	m3	237.6	-	-	-	-	237.6	128	30,413
2	Anti-termite treatment	m2	134.7	-	-	-	-	134.7	35	4,715
3	PCC 1:4:8 – under footings	m3	10.6	-	-	-	-	10.6	4,961	52,486
4	RCC M20 – Footings	m3	44.1	-	-	-	-	44.1	7,441	3,28,155
5	Reinforcement (TMT) – Footings	kg	3,528.0	-	-	-	-	3,528.0	80	2,80,758
6	Centring & shuttering – Footings	m2	84.0	-	-	-	-	84.0	466	39,144
7	RCC M20 – Columns up to plinth	m3	3.9	-	-	-	-	3.9	7,432	29,132
8	Reinforcement (TMT) – Columns up to plinth	kg	704.7	-	-	-	-	704.7	80	56,080
9	Centring & shuttering – Columns up to plinth	m2	43.5	-	-	-	-	43.5	466	20,271
10	RCC M20 – Plinth beam 230×300	m3	4.8	-	-	-	-	4.8	7,443	35,948
11	Reinforcement (TMT) – Plinth beam 230×300	kg	628.0	-	-	-	-	628.0	80	49,978
12	Centring & shuttering – Plinth beam 230×300	m2	42.0	-	-	-	-	42.0	466	19,576
13	Backfilling with excavated earth, compacted	m3	152.2	-	-	-	-	152.2	200	30,432
14	Plinth filling (earth/gravel) 300 mm, compacted	m3	40.4	-	-	-	-	40.4	740	29,905
15	PCC 1:4:8 – flooring bed 75 mm at ground level	m3	8.6	-	-	-	-	8.6	4,960	42,602
16	Disposal of surplus earth	m3	85.5	-	-	-	-	85.5	509	43,500
17	RCC M20 – Columns	m3	8.2	8.2	8.2	8.2	-	32.9	7,441	2,44,951
18	Reinforcement (TMT) – Columns	kg	1,481.3	1,481.3	1,481.3	1,481.3	-	5,925.3	80	4,71,536
19	Centring & shuttering – Columns	m2	91.4	91.4	91.4	91.4	-	365.8	466	1,70,444
20	RCC M20 – Beams 230×450	m3	5.2	5.2	5.2	5.2	-	20.9	7,446	1,55,775
21	Reinforcement (TMT) – Beams 230×450	kg	785.0	785.0	785.0	785.0	-	3,140.1	80	2,49,892
22	Centring & shuttering – Beams 230×450	m2	61.6	61.6	61.6	61.6	-	246.4	466	1,14,846
23	RCC M20 – Roof slab 125 mm (incl. sunshade/projection 5%)	m3	17.7	17.7	17.7	17.7	-	70.7	7,441	5,26,256
24	Reinforcement (TMT) – Roof slab 125 mm (incl. sunshade/projection 5%)	kg	1,591.2	1,591.2	1,591.2	1,591.2	-	6,365.0	80	5,06,528
25	Centring & shuttering – Roof slab 125 mm (incl. sunshade/projection 5%)	m2	141.4	141.4	141.4	141.4	-	565.8	466	2,63,653
26	RCC M20 – Lintels 230×150	m3	0.6	0.6	0.6	0.6	-	2.4	7,484	17,662

S.No	Description	Unit	Ground	First	Second	Third	Common	Total	Rate	Amount
27	Reinforcement (TMT) – Lintels 230×150	kg	41.5	41.5	41.5	41.5	-	166.2	80	13,222
28	Centring & shuttering – Lintels 230×150	m2	9.1	9.1	9.1	9.1	-	36.5	466	16,992
29	RCC M20 – Sunshades 600 mm	m3	0.5	0.5	0.5	0.5	-	2.0	7,501	15,001
30	Reinforcement (TMT) – Sunshades 600 mm	kg	35.3	35.3	35.3	35.3	-	141.1	80	11,230
31	Centring & shuttering – Sunshades 600 mm	m2	7.4	7.4	7.4	7.4	-	29.6	466	13,779
32	RCC M20 – Staircase	m3	2.0	2.0	2.0	-	-	6.0	7,441	44,647
33	Reinforcement (TMT) – Staircase	kg	200.0	200.0	200.0	-	-	600.0	80	47,748
34	Centring & shuttering – Staircase	m2	8.0	8.0	8.0	-	-	24.0	466	11,184
35	Brick masonry 230 mm in CM 1:6 – walls	m3	44.7	44.8	44.8	44.8	-	179.0	7,517	13,45,473
36	Brick partition 115 mm in CM 1:4 – walls	m2	9.3	9.3	9.3	9.3	-	37.3	901	33,594
37	Internal plaster 12 mm CM 1:6 – walls	m2	292.7	293.1	293.1	293.1	-	1,172.0	195	2,28,786
38	External plaster 20 mm CM 1:4 (2 coats) – outer walls	m2	157.4	136.1	136.1	136.1	-	565.6	313	1,76,859
39	Ceiling plaster 6 mm CM 1:3 – ceiling	m2	123.9	123.9	123.9	123.9	-	495.7	206	1,02,291
40	Vitrified floor tiles on CM 1:4 bed (incl. skirting)	m2	114.5	114.5	114.5	114.5	-	458.0	1,162	5,32,415
41	Wall tiles – toilets (2.1 m) & kitchen dado	m2	32.8	32.8	32.8	32.8	-	131.2	998	1,30,938
42	Granite – kitchen counter & staircase treads/risers	m2	7.8	7.8	7.8	1.8	-	25.2	2,445	61,614
43	Waterproofing – toilets	m2	9.6	9.6	9.6	-	-	28.8	154	4,435
44	Interior painting – putty, primer, 2 coats emulsion (walls + ceiling)	m2	416.6	417.0	417.0	417.0	-	1,667.7	150	2,50,161
45	Exterior painting – primer + 2 coats	m2	157.4	136.1	136.1	136.1	-	565.6	200	1,13,131
46	Main door with frame & hardware	nos	1.0	-	-	-	-	1.0	32,525	32,525
47	Room doors (flush) with frame & hardware	nos	2.0	3.0	3.0	3.0	-	11.0	14,525	1,59,775
48	Toilet doors (PVC/FRP) with frame	nos	2.0	2.0	2.0	2.0	-	8.0	8,525	68,200
49	Windows & ventilators with glass	m2	8.3	8.3	8.3	8.3	-	33.4	6,450	2,15,172
50	MS grills for windows	kg	125.1	125.1	125.1	125.1	-	500.4	106	53,142
51	Enamel paint – doors & grills	m2	21.3	20.8	20.8	20.8	-	83.7	155	12,976
52	Toilet – sanitary fittings set	nos	2.0	2.0	2.0	2.0	-	8.0	25,000	2,00,000
53	Toilet – water supply & drainage piping	nos	2.0	2.0	2.0	2.0	-	8.0	16,900	1,35,200

S.No	Description	Unit	Ground	First	Second	Third	Common	Total	Rate	Amount
54	Kitchen sink, tap & piping	nos	1.0	1.0	1.0	1.0	-	4.0	11,450	45,800
55	Electrical points (conduit, wiring, switches)	point	44.0	44.0	44.0	44.0	-	176.0	1,194	2,10,144
56	Distribution board with MCBs	nos	1.0	1.0	1.0	1.0	-	4.0	11,100	44,400
57	RCC M20 – Staircase to terrace + headroom	m3	-	-	-	1.2	-	1.2	7,441	8,929
58	Reinforcement (TMT) – Staircase to terrace + headroom	kg	-	-	-	120.0	-	120.0	80	9,550
59	Centring & shuttering – Staircase to terrace + headroom	m2	-	-	-	6.0	-	6.0	466	2,796
60	Waterproofing – toilets & terrace	m2	-	-	-	158.5	-	158.5	154	24,413
61	Brick partition 115 mm in CM 1:4 – terrace parapet 0.9 m	m2	-	-	-	42.6	-	42.6	901	38,426
62	Internal plaster 12 mm CM 1:6 – parapet inner face	m2	-	-	-	42.6	-	42.6	195	8,325
63	External plaster 20 mm CM 1:4 (2 coats) – parapet outer face	m2	-	-	-	42.6	-	42.6	313	13,333
64	Overhead tank 4000 L with fittings	litre	-	-	-	4,000.0	-	4,000.0	9	37,900
65	Earthing pits	nos	-	-	-	-	2.0	2.0	6,550	13,100
66	EB service connection & meter board	nos	-	-	-	-	1.0	1.0	15,000	15,000
67	Rain water harvesting pit (TN mandatory)	nos	-	-	-	-	1.0	1.0	20,000	20,000
68	Construction water (tanker loads)	load	-	-	-	-	112.0	112.0	700	78,400
69	Watchman & curing during construction	day	-	-	-	-	364.0	364.0	600	2,18,400
	TOTAL (before extras)									**86,34,049**

Area Statement

Floor	Built-up (sq ft)	Carpet (approx.)	Common / stair	Remarks
Ground Floor	1,450	1,132	113	2 bed, 2 toilet, kitchen, hall
First Floor	1,450	1,132	113	2 bed, 2 toilet, kitchen, hall
Second Floor	1,450	1,132	113	2 bed, 2 toilet, kitchen, hall
Third Floor	1,450	1,132	113	2 bed, 2 toilet, kitchen, hall
Total	**5,800**	**4,528**	**452**	

Payment Schedule (typical)

Stage	Description	%	Amount (Rs.)
1	Advance / Mobilization	10%	11,13,772
2	Foundation up to Plinth	15%	16,70,659
3	Ground Floor Roof Slab	14%	15,59,281
4	First Floor Roof Slab	14%	15,59,281
5	Second Floor Roof Slab	14%	15,59,281
6	Third Floor Roof Slab	13%	14,47,904
7	Finishing Works (plaster, flooring, painting)	15%	16,70,659
8	External Works & Handover	5%	5,56,886
	Total	**100%**	**1,11,37,723**

Materials (incl. wastage)

Material	Qty	Unit	Rate	Amount
TMT steel bars	21,958.03	kg	66	14,49,230
Bricks (chamber / wire-cut)	90,903.19	nos	10	9,09,032
Cement (PPC / OPC 53)	2,206.39	bag	400	8,82,556
Floor tiles (vitrified)	524.33	m2	750	3,93,249
Centring sheets / props / plywood (hire + consumables)	1,443.53	m2	250	3,60,883
M-Sand (concrete / masonry)	158.59	m3	1,850	2,93,405
Blue metal / jelly 20 mm	163.53	m3	1,600	2,61,651
Windows (aluminium / UPVC with glass)	33.36	m2	6,000	2,00,160
Sanitary set per toilet (EWC, basin, taps, shower)	8.0	nos	25,000	2,00,000
Electrical point (conduit, wire, switch, box)	176.0	point	900	1,58,400
Interior paint system (putty + primer + 2 coats emulsion)	1,751.13	m2	90	1,57,601
Internal flush door with frame	11.0	nos	12,000	1,32,000
Plumbing pipes & fittings per toilet	8.0	nos	12,000	96,000
Wall tiles (toilet / kitchen dado)	141.7	m2	650	92,102
P-Sand (plastering)	40.99	m3	2,150	88,119
Exterior paint system (primer + 2 coats)	593.94	m2	120	71,273
Granite (kitchen top, steps)	27.72	m2	1,950	54,054
Toilet door (PVC / FRP) with frame	8.0	nos	6,000	48,000
MS window grills	500.4	kg	95	47,538
Distribution board + MCBs (per floor)	4.0	nos	10,000	40,000
Kitchen sink + tap + piping	4.0	nos	9,000	36,000
Overhead water tank	4,000.0	litre	9	36,000
Main door with frame (complete)	1.0	nos	30,000	30,000
Door hardware set (hinges, locks, handles)	20.0	nos	1,500	30,000
Jelly 40 mm (PCC)	17.37	m3	1,400	24,323
Filling earth / gravel	40.41	m3	500	20,206

Material	Qty	Unit	Rate	Amount
Rain water harvesting pit (complete)	1.0	nos	20,000	20,000
Waterproofing (toilets, terrace)	187.32	m2	100	18,732
Binding wire	213.18	kg	80	17,055
EB service connection & meter board	1.0	nos	15,000	15,000
Earthing pit	2.0	nos	6,000	12,000
Enamel paint (doors, grills)	83.72	m2	95	7,953
Tile adhesive / grout	131.2	m2	60	7,872
Anti-termite chemical treatment	134.71	m2	35	4,715

Labour (man-days × TN day wage)

Labour trade	Man-days	Wage	Amount
Helper – male (Chithal)	834.82	800	6,67,885
Mason (Kothanaar)	376.2	1,100	4,13,795
Helper – female (Chithal)	488.56	700	3,42,020
Watchman / curing	364.0	600	2,18,400
Centring carpenter	173.18	1,000	1,73,224
Bar bender	127.93	1,000	1,27,911
Painter	114.04	1,000	1,14,011
Tile layer	66.62	1,200	79,965
Electrician	36.68	1,100	40,348
Plumber	31.0	1,100	34,100
Carpenter (doors / windows)	25.0	1,100	27,509
Welder / fabricator	4.0	1,000	4,003